BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37095/CALL-3

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/28/2019-20, Date: 17.03.2020

Name of Work:Improvements to Drains and Laying covering slabs at Dasarahalli Near BBMP Office side drains in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of H S Palaksha Murthy ( )	
				In Figures	In Words
1	37.8	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	135.65	Rupees One Hundred Thirty Five and Sixty Five Paise Only
2	27.36	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 13/ Item No. 4.3/ PWD SR 2018-19	Cum	5323.75	Rupees Five Thousand Three Hundred Twenty Three and Seventy Five Paise Only
3	16.2	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 25/ Item No. 5.9/ PWD SR 2018-19	Sqm	5721.31	Rupees Five Thousand Seven Hundred Twenty One and Thirty One Paise Only
4	16.05	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	5539.75	Rupees Five Thousand Five Hundred Thirty Nine and Seventy Five Paise Only
5	240	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Page No. 26/ Item No. 5.27/ PWD SR 2018-19	Sqm	951.64	Rupees Nine Hundred Fifty One and Sixty Four Paise Only
6	27	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm	220.17	Rupees Two Hundred Twenty and Seventeen Paise Only
7	27	Providing precast slab of 250mm thick including cost of all materials, labour, curing,transportation,loading,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	5333.48	Rupees Five Thousand Three Hundred Thirty Three and Forty
8	453.6	Providing precast slab of 100 mm thick including cost of all materials, labour, curing,transportation,loading,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	2300.54	Rupees Two Thousand Three Hundred and Fifty Four Paise Only
9	37.8	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	59.48	Rupees Fifty Nine and Forty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/06

Signature of the contractor

Executive Engineer